




# Terapro VTS (unreinforced)

A detailed architectural floor plan in white lines on a dark background, showing various rooms, corridors, and structural elements. The plan is used as a background for the title text.

# Material Estimating Guide



**Substrate Preparation**

Pro Paste: 5–kg can

Number of pails needed: \_\_\_\_\_

Deck Area (sf): \_\_\_\_\_

Typical Paste Coverage: 0.13 kg/sf  
(1.4 kg/m<sup>2</sup>) per 1 mm of thickness

Pro Prep 1–gal or 5–gal can


Number of pails needed: \_\_\_\_\_

Flashing Area (sf): \_\_\_\_\_

**FLASHING SYSTEM**

	area to be covered (sf)	÷	s/f coverage per unit	=	# of units needed	+	waste factor*	=	total # of units	Pro Catalyst Liquid (cups) (see catalyst chart)
<b>Primer Layer (concrete substrate)</b> Pro Primer W (10–kg pail) Consumption (min): 0.037 kg/sf Coverage (min): 270 sf/pail		÷	270	=		+		=	_____	_____
									<b>Pails</b>	<b>Cups</b>
<b>Flashing Layer (Base &amp; Top Coats)</b> Terapro Flashing Resin (10–kg pail) Consumption (min): 0.31 kg/sf Coverage (min): 32 sf/pail		÷	32	=		+		=	_____	_____
									<b>Pails</b>	<b>Cups</b>
<b>Reinforcing Fleece (Pro Fleece)</b> 12" x 164' (164 sf)		÷	164	=		+		=	_____	n/a
									<b>Rolls</b>	
<b>Finish Layer</b> Pro Color Finish (10–kg pail) Consumption (min): 0.046 kg/sf Coverage (min): 215 sf/pail		÷	215	=		+		=	_____	_____
									<b>Pails</b>	<b>Cups</b>

# Terapro VTS Unreinforced – Unoccupied Space



## FIELD MEMBRANE

	area to be covered (sf)	s/f coverage per unit	# of units needed	waste factor*	total # of units	Pro Catalyst Liquid (cups) (see catalyst chart)
<b>Primer Layer (concrete substrate)</b> Pro Primer T (10 kg pail) Consumption (min): 0.037 kg/sf Coverage (min): 270 sf/pail	÷	270	=	+	=	Pails Cups
<b>Waterproofing/Wearing Layer</b>  Terapro VTS Resin (10 kg pail) Consumption (min): 0.14 kg/sf Coverage (min): 71 sf/pail	÷	71	=	+	=	Pails Cups
Terapro VTS Quartz Filler (50 lbs bag) Coverage (min): 71 sf/pail	÷	71	=	+	=	Bags n/a
<b>Surfacing Aggregate</b> VTS Quartz (50 lbs bag) Consumption (min): 1 lb/sf Coverage: 50 sf/bag	÷	50	=	+	=	Bags n/a
<b>Color Finish Layer</b> Pro Color Finish (10 kg pail) Consumption (min): 0.07 kg/sf Coverage (min): 144 sf/pail	÷	144	=	+	=	Pails Cups

## CATALYST FOR FLASHING & FIELD

	total # of cups above		cups per container		total # of units
Pro Catalyst Liquid 2.5 kg container (10 cups)		÷	10	=	<u>          </u> Containers

## WASTE AND OVERAGE FACTORS

RESIN TYPE	4" COVER	9" COVER	18" COVER
Pro Primer/Pro Color	0.1 kg	0.55 kg	1.1 kg
Terapro Flashing and Base Resin	0.1 kg	0.75 kg	1.5 kg

## LAP TREATMENT OVERAGE FACTORS (avg. overage per fleece roll width in %)

PRODUCT	12"	41"
Terapro Flashing and Base Resin	12%	3.5%
Pro Fleece	17%	5%

Coverage quantities are based upon minimum weight and coverage requirements. The above estimates do not include provisions for crack/joint treatment, detailing, rough absorbent surfaces, or waste (including material required for saturation of disposable roller covers and fleece overlaps).

To Ensure that an adequate quantity of material is purchased for a project, a waste factor should be included in all estimates. The contractor is best qualified to determine actual waste factors.

# Pro Catalyst Liquid Mixing Charts

### Pro Catalyst Liquid Mixing Chart Pro Primer W and Pro Primer T

Resin Quantity	Ambient Temperature 77°F to 95°F (25°C to 35°C)		Ambient Temperature 41°F to 77°F (5°C to 25°C)		Ambient Temperature 32°F to 41°F (0°C to 5°C)	
	tablespoons	cups	tablespoons	cups	tablespoons	cups
1 kg (1 liter)	2	n/a	4	n/a	6	n/a
10 kg (10 liters)	n/a	1	n/a	2	n/a	3

Substrate temperature range for application of Pro Primers is 32°F to 95°F (0°C to 35°C).

### Pro Catalyst Liquid Mixing Chart Pro Color Finish

Resin Quantity	Ambient Temperature 59°F to 95°F (15°C to 35°C)		Ambient Temperature 41°F to 59°F (5°C to 15°C)		Ambient Temperature 32°F to 41°F (0°C to 5°C)	
	Tablespoons	Cups	Tablespoons	Cups	Tablespoons	Cups
1 kg (1 liter)	2	n/a	4	n/a	6	n/a
10 kg (10 liters)	n/a	1	n/a	2	n/a	3

Substrate temperature range for application of Pro Color Finish is 32°F to 95°F (0°C to 35°C).

**Pro Catalyst Liquid Mixing Chart  
Summer Grade  
Terapro Base Resin and Terapro Flashing Resin**

Resin Quantity	Ambient Temperature 68°F to 104°F (20°C to 40°C)		Ambient Temperature 59°F to 68°F (15°C to 20°C)	
	tablespoons	cups	tablespoons	cups
1 kg (0.72 liter)	2	n/a	4	n/a
10 kg (7.2 liters)	n/a	1	n/a	2

Substrate temperature range for application of Summer Grade Parapro and Terapro resins is 59°F to 122°F (15°C to 50°C).

**Pro Catalyst Liquid Mixing Chart  
Winter Grade  
Terapro Base Resin and Terapro Flashing Resin**

Resin Quantity	Ambient Temperature 59°F to 68°F (15°C to 20°C)		Ambient Temperature 41°F to 59°F (5°C to 15°C)		Ambient Temperature 23°F to 41°F (-5°C to 5°C)	
	tablespoons	cups	tablespoons	cups	tablespoons	cups
1 kg (0.72 liter)	2	n/a	4	n/a	6	n/a
10 kg (7.2 liters)	n/a	1	n/a	2	n/a	3

Substrate temperature range for application of Winter Grade Parapro and Terapro resins is 23°F to 77°F (-5°C to 25°C).

**Pro Catalyst Liquid Mixing Chart  
Terapro VTS Resin/Filler (full batch with 10 kg of VTS Resin and full bag of VTS Filler)**

Ambient Temperature 77°F to 95°F (25°C to 35°C)	Ambient Temperature 41°F to 77°F (5°C to 25°C)	Ambient Temperature 32°F to 41°F (0°C to 5°C)
1 cup	2 cups	3 cups

Substrate temperature range for application of Terapro VTS Resin is 32°F to 122°F (0°C to 50°C).

**Pro Catalyst Liquid Mixing Chart  
Pro Paste Resin**

Resin Quantity	Ambient Temperature 77°F to 95°F (25°C to 35°C)		Ambient Temperature 41°F to 77°F (5°C to 25°C)		Ambient Temperature 32°F to 41°F (0°C to 5°C)	
	Tablespoons	Cups	Tablespoons	Cups	Tablespoons	Cups
1 kg (0.72 liter)	2	n/a	4	n/a	6	n/a

Substrate temperature range for application of Pro Paste Resin is 32°F to 122°F (0°C to 50°C).



**Siplast**

1000 Rochelle Blvd.  
Irving, Texas 75062  
469-995-2200  
Facsimile: 469-995-2205

Customer Service in  
North America:  
Toll Free 1-800-922-8800

[www.siplast.com](http://www.siplast.com)

In Canada:  
201 Bewicke Ave., Suite 208  
Vancouver, BC,  
Canada V7M 3M7  
604-929-7687



For information on Siplast  
Roofing and Waterproofing  
Systems, scan our QR Code.